

Manual Pressure Test Pump

This hand test pump is designed for manually pressure testing systems and components. It includes a pressure gauge for accurate monitoring and a lever handle for manual operation.



Overview

Professional Pressure Testing Solution

This manual pressure test pump is designed for reliable hydraulic leak testing in various industrial and residential systems, including heating, oil installations, and air-conditioning. Featuring a robust, manually operated mechanism, it allows for accurate pressure monitoring and control up to 50 bar. The unit is built for durability with a lubricated plunger and replaceable seals, ensuring consistent performance for professional plumbing and HVAC applications.

Technical Specifications

Pressure Range

50 bar

Max Pressure

Suitable Applications

Heating Systems, Oil Installations, Air-Conditioning, Sprinkler Systems, Pipeline Testing

Features

Maintenance & Design

- Lubricatable pump plunger
- Replaceable seals
- High-pressure hose included
- Includes connectors
- Efficient running needle valves

Operation Type

Manual